





# Installation Instructions Challengers® Model CH4095 Centerline Pipe Wall Barrier

**Installation Preparation** 

Recommended Crew:	One (1) adult
Installation Time:	0.5 installation-hours
Use Zone:	Refer to Master Drawing
User Group Age (years):	ASTM/CSA: 2-12, EN: 2-14


ICON KEY	,		
	Fully Tighten Hardware		Add 1 Drop of Thread Locking Adhesive
	Do <u><b>Not</b></u> Fully Tighten Hardware		Pour Concrete
	Drill		Dig Footing Holes
	Hammer	z	Critical Fall Height





Model CH4095 PA 835

## Installation Instructions



Model CH4095 PA 835

### Installation Instructions

\_\_Notes Before You Begin: Do not over tighten bolts during assembly, only snug tighten them until assembly is complete.

# Carefully read and understand these installation instructions before you begin.

**Step 1:** Before attempting to assemble your equipment, please review all installation information carefully. Should you experience any difficulty during the installation process, please call us at the phone number shown on the last page of these instructions.

Step 2: Separate and identify all components and hardware.

#### Attach the clamps to the barrier.

**Step 3:** See **Detail A**. Attach a shown. Make sure the clamps open the same direction.

#### Attach the clamps to the support posts.

**Step 4:** See **Detail B.** Lift the barrier into position against the deck. Close the clamps around the support posts. Align the barrier plates with the deck. Attach as shown. Snug tighten connection only. The location of the clamp may need to be changed to align deck connection holes or resolve clamp position conflicts.

**Note:** To avoid clamp interference, the deck has been provided with an upper and lower set of holes. Choose the either set of holes that works best with your clamp placement condition.

#### Attach the bottom of the barrier to the deck.

Step 5: See Detail C. Attach as shown.

#### Final Details.


**Step 6:** Plumb and level the component. Tighten **all** fasteners. Fully tighten all fasteners according to tightening torque specifications.

#### **Torque Specifications:**

Bolts and nuts - Snug tighten and then tighten an additional one half turn.

**Step 7:** Install drive rivets. See **Detail D**. After the equipment assembly is complete, install a drive rivet in each clamp to permanently secure it to the support post. Using a 1/4" drill bit, drill through the clamp and support post. Insert the drive rivet into drilled hole until the head of the rivet is against the surface of the clamp. Using a hammer, drive the pin of the rivet until it is flush with the surface of the rivet head.

**Note:** This step should be executed after structure has been assembled and properly footed.



#### **CH4095 - CENTERLINE PIPE WALL BARRIER**

PART NO.	DESCRIPTION	QTY.
AAU0556	CLAMP - 3-1/2" CENTERLINE DIE CAST	2
AEN0224	BARRIER - 30-1/2" x 41-7/8" CENTERLINE PIPEWALL	1
BAD0085	THREAD LOCKING ADHESIVE	1
BAE0020	RIVET - 1/4" x 11/16" DRIVE	2
BAE0595	WASHER - 3/8" SAE FLAT	2
BAE0600	WASHER - 1" O.D. FLAT	4
BAE0620	NUT - 3/8"-16 LOCK w/ NYLON CAP	2
BAE0662	BOLT - 3/8"-16 x 1-1/4" TAMPER RESISTANT	2
BAE0664	BOLT - 3/8"-16 x 1" BUTTON HEAD - SS	4



www.playworldsystems.com

